

# Deep Photometric Survey of IC2391

By D. BARRADO y NAVASCUÉS<sup>1†</sup>, J. R. STAUFFER<sup>1</sup>  
AND C. BRICEÑO<sup>2</sup>

<sup>1</sup>Harvard-Smithsonian Center for Astrophysics, 60 Garden St., Cambridge, MA02138, USA

<sup>2</sup>Yale University, USA

We present a deep survey of the young southern cluster IC2391. We have covered 2 sq. degrees in the R,I filter. We have selected several dozens VLM stars and BD candidates based on the position of these objects in the Color-Magnitude Diagram.

---

## 1. Introduction

The open cluster IC2391 ( $\alpha=8^{\text{h}} 38.8^{\text{m}}$ ,  $\delta=-52^{\circ}53'$ ) has adequate characteristics to carry out a survey in order to look for very low mass stars (VLM) and brown dwarfs (BD) candidates. It is a very young cluster, considerably younger than the Pleiades (the standard age is  $\sim 30$  Myr, versus the often quoted standard age for the Pleiades of 70-80 Myr). In addition, its distance is approximately the same as the Pleiades and it is not spread over a large area, making feasible to cover a significant fraction of the cluster in few nights.

We carried out a deep photometric survey in January 1998, using the cousin R and I filters, and covering a large fraction of the cluster, around 2 square degrees. We used the CTIO 4 meter Blanco telescope and the Big Throughput Camera, a mosaic detector composed by 4 different CCDs of  $2048 \times 2048$  pixels each. One CCD covers  $14.7 \times 14.7$  arc-minutes and their edges are separated from each other by a distance of 5.4 arc-minutes.

We observed 9 different fields around the center of the cluster, avoiding the bright stars in the center. Figure 1 shows the portions of the sky covered by our survey, together the 6 brightest stars on the field. Table 1 lists the positions of the center of each field. Exposure times are also listed in the same table, as well as the magnitude limits.

Since our nights were not photometric, we used an observation collected several days before at the CTIO 0.9m telescope to calibrate the data. Additional calibrations were derived from other observations taken on April. All agree quite well and we have estimated the error in our photometry as better than 0.05 mag.

## 2. Membership in the Cluster

Candidates to be members of the clusters were selected based on the R,I Color-Magnitude diagram (CMD). Figure 2 shows the objects detected in our survey (dots). An empirical Zero Age Main Sequence (ZAMS) and a 30 Myr isochrone (D'Antona & Mazzitelli 1994) are also displayed. The ZAMS was built by tracing the lower envelope of Color-Magnitude Diagram of nearby dK and dM stars (Leggett 1992). We have used these curves to select our best candidate members. Since the real age of the cluster is not known (Stauffer et al. 1998 have obtained an age of 125 Myr for the Pleiades based on the lithium depletion boundary. See Barrado y Navascués et al. 1999 for a discussion about the new age scale for young open clusters) and, therefore, where the MS lies, we selected stars below and above the 30 Myr isochrone, but considerably brighter than the

<sup>†</sup> Present address: MPI für Astronomie, Königstuhl 17, D-69117 Heidelberg, Germany




FIGURE 1. Graphic representation of the area of the sky around IC2391. The six stars brighter than  $V=6^{\text{mag}}$  are shown. Our fields appear as solid ( $\#1, \#2, \#4, \#5, \#6$ ) and dotted ( $\#1', \#3', \#5'$ ) squares. Candidates are shown as crosses.

| Field | RA<br>(2000.0)<br>(h m s) | DEC<br>( $^{\circ}$ ' ") | Exp. Time      |                | Mag. limit |       |
|-------|---------------------------|--------------------------|----------------|----------------|------------|-------|
|       |                           |                          | $R_c$<br>(sec) | $I_c$<br>(sec) | $R_c$      | $I_c$ |
| #1    | 08:40:10                  | -53:20:01                | 2880           | 1200           | 23.1       | 21.7  |
| #1'   | 08:40:32                  | -53:19:58                | 1200           | 600            | 23.1       | 21.5  |
| #2    | 08:43:52                  | -53:26:25                | 1440           | 600            | 23.1       | 21.3  |
| #3    | 08:38:11                  | -52:46:44                | 960            | 960            | 22.8       | 19.4  |
| #3'   | 08:39:46                  | -52:31:03                | 1200           | 600            | 23.5       | 22.0  |
| #4    | 08:42:55                  | -52:46:59                | 600            | 1440           | 22.8       | 20.8  |
| #5    | 08:36:30                  | -53:20:00                | 1200           | 600            | 23.1       | 21.8  |
| #5'   | 08:37:04                  | -53:14:49                | 274            | 400            | 23.0       | 21.8  |
| #6    | 08:45:14                  | -52:56:50                | 1200           | 600            | 23.5       | 22.1  |

TABLE 1. Observed fields

ZAMS. Based on the comparison with the data from Simon & Patten (1996) -and references therein- and Pavlovsky & Patten (1998), represented as filled and empty triangles in Figure 3a, respectively, our best candidates for IC2391 membership are those VLM stars and BD which are located in the upper part of our CMD. However, due to the lack of additional information (e.g. proper motions, spectroscopy, location of the lithium depletion boundary), we cannot rule out that, for the same color, fainter objects in our




FIGURE 2. Color-Magnitude diagram. Our member candidates are shown as filled circles. A ZAMS (empirical, obtained from field stars) and a 30 Myr isochrone (D’Antona & Mazzitelli 1994) appear as solid lines. We used the 30 Myr isochrone to select the candidates. Note the gap between  $18 \leq I_c \leq 19.5$  magnitudes.

sample of candidates belong to the cluster. A spectroscopic follow-up of this sample will allow us to establish the locus of the MS of the cluster and an accurate age.

A comparison between our candidates and members of the clusters  $\alpha$  Per and the Pleiades is presented in Figure 3b. We used the distances and reddening by Pinsonneault et al. (1998), derived from fitting a MS to Color-Magnitude diagrams of actual members. We have plotted the data using other values of the distances [as measured with Hipparcos -Mermilliod et al. (1997)- and from Lyngå (1987)] and the figure does not change in a significant way. If our survey contains an important fraction of IC2391 members and if our assumed distances and reddenings are correct, then IC2391 is not apparently significantly younger than  $\alpha$  Per. Recent measurement of lithium in  $\alpha$  Per members (Barrado y Navascués et al. 1999) indicates that it could be as old as  $\sim 85$  Myr old.

The lack of objects in the IC2391 locus in the range  $18 \leq I_c \leq 19.5$  is puzzling. It could indicate a sudden cut-off in the mass function of the clusters. Using the D’Antona & Mazzitelli (1994) models, it would appear for BD at  $0.03 M_{\odot}$ . It is also intriguing the detection of a significant number of objects redder than the ZAMS and fainter than  $I \sim 19.5$  mag. These are real detections and the photometry looks good enough. We have tried to perform several test to confirm or reject their membership. Firstable, there is a clear gap between the field stars and those objects detected in the position of the IC2391 locus. In addition, our candidates are concentrated at the center of the cluster. Moreover, despite the scarcity of data, the gap does not appear for field stars slightly blueward of the ZAMS. An histogram for stars in field #1 having  $19.5 \leq I_c \leq 20.5$  mag. shows that there is a clear drop at  $(R-I) \sim 2.2$  and that there is a high number of objects in the  $(R-I)$  bins corresponding to the position of IC2391. This situation induces us to




FIGURE 3. **a** Comparison between IC2391 candidates by Simon & Patten (filled triangle), Pavlovsky & Patten candidates (empty triangles), and our IC2391 VLM and BD candidates (filled circles). **b** Comparison between Pleiades members (empty circles),  $\alpha$  Per members (crosses), and our IC2391 VLM and BD candidates (filled circles). These clusters have standard ages of  $\sim 70$ , 50 and 30 Myr, respectively.

consider them as possible extremely low mass BD, members of the cluster, which deserve further observations to try to confirm their status.

DBN acknowledge the support by the “Real Colegio Complutense at Harvard University”, the MEC/Fulbright Commission, and the European Union.

#### REFERENCES

- Barrado y Navascués, D., Stauffer, J.R., Bouvier, J. 1999, *Astrophysics and Space Science*
- D’Antona, F., & Mazzitelli, I., 1994, *ApJS* 90, 467
- Legget, S.K., 1992, *ApJS* 82, 351
- Lyngå, G., *Catalogue*, 5th edition (Strasbourg)
- Mermilliod, J.-C., Turon, C., Robichon, N., Arenou, F., Lebreton, Y., 1997, *Proceedings of the ESA Symposium ‘Hipparcos - Venice ’97’*, Venice, Italy, ESA SP-402 (July 1997), p. 643-650
- Pavlovsky, C., & Patten, B.M., 1997, *AAS* 191. 8015
- Pinsonneault, M.H., Stauffer, J.R., Soderblom, D.R., King, J.R., Hanson, R.B., 1998, *ApJ* 504, 170
- Simon, T. & Patten, B.M., 1998, *PASP* 110, 283
- Stauffer, J.R., Schultz, G., Kirckpatrick, J.D., 1998, *ApJ Letters* 499, 199